PURPOSE

To run A.D.A. in one Max-Migold building for about six weeks, record its power and water in detail, automate the routine switching, and decide together whether and how to extend it. This is a draft to discuss on our call; every item below can be adjusted.

SCOPE

Site	One building or block, chosen together: ideally one with frequent changeovers, a borehole and overhead tank, and an inverter.
Duration	About six weeks: one week of setup, four weeks of operation, one week of review.
What's monitored	Power source and changeovers, mains voltage, generator run-hours, inverter use, tank level and pump cycles.
What's automated	Borehole pump on tank level; shedding of agreed heavy loads on inverter; cutting of sensitive loads on voltage spikes. The list of loads is agreed before installation.
Hardware	Low-cost, widely available parts: an ESP32 controller board, relay module, tank level sensor, isolated voltage/source sensor, enclosure and wiring. A.D.A. provides the full parts list and configures everything. Purchase of the parts and who funds them is agreed before installation.
Out of scope	Changes to the building's generator, inverter or changeover; billing residents.

TIMELINE

WEEK 0
Agree & survey
Choose the building, walk through the distribution board and pump setup, agree loads and success measures.

WEEK 1
Install
Fit controller, tank sensor and hub. Mains connections by a qualified electrician. Dashboard access set up.

WEEKS 2–5
Operate
A.D.A. runs and logs. Short weekly check-in and a weekly summary.

WEEK 6
Review
Results, findings and feedback. Decide on next steps together.

A.D.A. WILL

1. Provide the hub software and dashboard for the pilot.
2. Supply the hardware parts list and configure the controller and sensors.
3. Coordinate installation with a qualified electrician for any mains work.
4. Monitor the system and fix software issues during the pilot.
5. Send a weekly summary and a final report.

MAX-MIGOLD WILL

1. Choose the building and arrange access to the distribution board and pump.
2. Obtain the hardware parts from the A.D.A. parts list, as agreed.
3. Name one contact on site.
4. Provide Wi-Fi access (or allow a dedicated hotspot).
5. Share how diesel and water are handled today, so results can be compared.
6. Give honest feedback at the weekly check-ins.

Hardware funding, installation costs and any pilot fee are to be agreed on our call and confirmed in writing before installation.

HOW WE'LL MEASURE SUCCESS

MEASURE	HOW IT'S RECORDED
Generator hours	Run-hours per day from the changeover log, compared with the building's usual diesel use.
Avoidable generator time	Hours the generator ran while the inverter still had plenty of charge.
Water	Number of pump cycles, overflows and dry-tank events, against the previous weeks as reported by the site.
Battery protection	Lowest battery level each night and how often heavy loads were shed.
Equipment protection	Voltage spikes detected and loads cut.
Team experience	Feedback from the site contact and managers: was it useful, what's missing.

WHAT YOU RECEIVE

Live dashboard

For the building throughout the pilot, on phone, tablet or wall screen, with access for your team.

Weekly summary

Hours on each power source, generator and diesel estimate, pump activity, spikes, and anything unusual.

Final report

Six weeks of findings with recommendations for the building, and a proposal for next steps if it makes sense.

RISKS AND HOW THEY'RE HANDLED

Controller or Wi-Fi failure	Relays fall back to safe states; the building runs exactly as it does today. The dashboard shows "not live".
Wrong load switched	Only loads agreed in writing are connected. Rules can be paused from the dashboard at any time.
Electrical safety	No mains work by anyone other than a qualified electrician; installation reviewed with your site contact.

NEXT STEPS

1. **Monday call (5:30 pm):** live demo, your current setup, and questions.
2. **Agree the building** and a date for a short site survey.
3. **Confirm scope, parts and terms** in writing.
4. **Obtain parts, install and start** the six-week pilot.

For Max-Migold · name, signature, date

For A.D.A. · Ajala David, signature, date

Contact
Ajala David
Founder, A.D.A.

+234 916 107 8549 · call or WhatsApp
segdav1228@gmail.com