# What a pilot costs, for one building

Honest ranges. The exact figure depends on how many circuits the building has and what is already there; it is fixed after a short site visit.

1 · PARTS

**₦400k–₦800k**

Bought by you, or by us with your money and every receipt handed over. No markup on parts.

2 · INSTALLATION & SETUP

**₦150k–₦250k**

**FREE FOR THE PILOT**

Wiring with your electrician, rules, dashboard, phone alerts, training.

3 · MONTHLY SUPPORT

**₦20k–₦30k**

Monitoring, updates, weekly reports. Only after the pilot, and only if you continue.

## Parts, line by line (estimates)

| PART | WHAT IT DOES | ESTIMATE |
|---|---|---|
| **Controller + relay board** | ESP32 controller that reads the building and switches loads | ₦15k – ₦30k |
| **Contactors × 3 (25–40 A)** | Safely switch the borehole pump and heavy loads such as ACs | ₦45k – ₦120k |
| **Power meters × 3** | Voltage, current and energy per circuit (PZEM-004T class) | ₦40k – ₦75k |
| **Diesel tank level sensor** | Measured litres; catches siphoning and short deliveries | ₦60k – ₦150k |
| **Inverter data reader** | Battery % and current from the inverter's RS485 port, or a shunt | ₦15k – ₦60k |
| **Enclosure, breakers, cabling** | Lockable panel, DIN rail, protection and wiring | ₦70k – ₦150k |
| **Hub computer** | Mini-PC that runs A.D.A. in the building, offline. An existing computer can do it | ₦150k – ₦220k |
| **Total parts** | | ≈ ₦400k – ₦800k |

### Cheaper way to start

**Monitoring only, no switching:** controller, power meters, diesel sensor, inverter reader and hub. About **₦330k – ₦640k**, less if an existing computer runs the hub. You see the diesel, power and battery picture first and add switching later.

### How it pays back

If A.D.A. stops **20 litres a week** being wasted, siphoned or short-delivered, at ₦1,300 per litre that is about **₦113,000 a month**. The parts pay back in roughly **4 – 7 months**, before counting generator hours saved or equipment protected.

## The pilot

| | |
|---|---|
| **Scope** | One building you choose, for 4 – 6 weeks |
| **You cover** | The parts (receipts provided) and an electrician's time for the 230 V wiring |
| **We cover** | Installation and setup, the dashboard, phone alerts, weekly reports, and fixes during the pilot |
| **In return** | Honest feedback, and if it works, permission to say Max-Migold piloted A.D.A. |
| **After the pilot** | You keep the parts. Continue with monthly support, or stop with no further cost |

All prices are estimates for November 2026 and move with the naira and suppliers. Final quote after a site visit. Electrical work on mains is done by a qualified electrician.