What a pilot costs, for one building

Honest ranges. The exact figure depends on how many circuits the building has and what is already there; it is fixed after a short site visit.

1 · PARTS

~~₦400k–₦800k~~

Bought by you, or by us with your money and every receipt handed over. No markup on parts.

2 · INSTALLATION & SETUP

~~₦150k–₦250k~~

FREE FOR THE PILOT

Wiring with your electrician, rules, dashboard, phone alerts, training.

3 · MONTHLY SUPPORT

~~₦20k–₦30k~~

Monitoring, updates, weekly reports. Only after the pilot, and only if you continue.

Parts, line by line (estimates)

PART	WHAT IT DOES	ESTIMATE
Controller + relay board	ESP32 controller that reads the building and switches loads	**~~₦15k – ₦30k~~**
Contactors × 3 (25–40 A)	Safely switch the borehole pump and heavy loads such as ACs	**~~₦45k – ₦120k~~**
Power meters × 3	Voltage, current and energy per circuit (PZEM-004T class)	**~~₦40k – ₦75k~~**
Diesel tank level sensor	Measured litres; catches siphoning and short deliveries	**~~₦60k – ₦150k~~**
Inverter data reader	Battery % and current from the inverter's RS485 port, or a shunt	**~~₦15k – ₦60k~~**
Enclosure, breakers, cabling	Lockable panel, DIN rail, protection and wiring	**~~₦70k – ₦150k~~**
Hub computer	Mini-PC that runs A.D.A. in the building, offline. An existing computer can do it	**~~₦150k – ₦220k~~**
Total parts		**≈ ~~₦400k – ₦800k~~**

Cheaper way to start

Monitoring only, no switching: controller, power meters, diesel sensor, inverter reader and hub. About **~~₦330k – ₦640k~~**, less if an existing computer runs the hub. You see the diesel, power and battery picture first and add switching later.

How it pays back

If A.D.A. stops **20 litres a week** being wasted, siphoned or short-delivered, at ₦1,300 per litre that is about **~~₦113,000~~ a month**. The parts pay back in roughly **4 – 7 months**, before counting generator hours saved or equipment protected.

The pilot

Scope	One building you choose, for 4 – 6 weeks
You cover	The parts (receipts provided) and an electrician's time for the 230 V wiring
We cover	Installation and setup, the dashboard, phone alerts, weekly reports, and fixes during the pilot
In return	Honest feedback, and if it works, permission to say Max-Migold piloted A.D.A.
After the pilot	You keep the parts. Continue with monthly support, or stop with no further cost

All prices are estimates for November 2026 and move with the naira and suppliers. Final quote after a site visit. Electrical work on mains is done by a qualified electrician.